ERL2022, October 3-6, 2022, Cornell, SRF/25



# **Horizontal test of SRF gun #2 at KEK**

October 5 (Wed), 2022

Taro Konomi<sup>\*</sup>, Eiji Kako, Kensei Umemori, Hiroshi Sakai, Yoshinari Kondo, Xudong Wang, Hitoshi Inoue, Mika Masuzawa, Kazufumi Hara, Akio Terashima, Toshikazu Takatomi, Ryuichi Uek, Kenji Hosoyama, Kiyosumi Tsuchiya, Yosuke Honda, Mathieu Omet (KEK)

\*Current affiliation is Michigan State University (MSU) - FRIB.



### Outline



- Introduction
  - Cavity Structure
- Vertical test results
- Horizontal test
  - Preparation for Horizontal test setup
  - Horizontal test results
- Summary
- Future plan

## **Cavity Parameter**



- KEK SRF gun was designed to demonstrate fundamental performance of SRF gun.
- ERL parameters are used to design KEK SRF gun.



Parameter	Value
RF frequency	1.3 GHz
Accelerating Voltage (Vc)	2 MV
Geometrical Factor	133.1 W
Surface Peak Electric Field (E <sub>sp</sub> ) @Vc=2MV	41.9 MV/m
Surface Peak Magnetic Field (H <sub>sp</sub> ) @Vc=2MV	92.4 mT
H <sub>sp</sub> /E <sub>sp</sub>	2.2 mT/(MV/m)
Z <sub>ESP</sub> *	241.3
	$E_{sn} = Z_{FSP} \sqrt{Q_0 P_{loss}}$

## **Cavity Field**





### **Vertical test results**



- Cavity polished by EP and applied HPR.
- w/o cathode rod: Esp = 76 MV/m. Hsp=167 mT.
- w/ cathode rod: Esp = 61.5 MV/m, Low Q<sub>0</sub> due to lack of choke tuning.





HPR nozzle for Acc. cell







Cathode rod

HPR nozzle for choke cell



## **Horizontal test setup**



- Use multi-purpose cryostat for Horizontal test and beam test.
- Gun cavity was cooled 6 times. High gradient performance was measured 4 times.
- Preparing components (SC magnet, 90deg. Bend, beam monitors) for beam test.





#### Helium jacket with frequency tuner



- Mechanical tuner was designed compact to fit multi-purpose cryostat, and the tuning range is 450 kHz.
- 2 Piezo tuner is installed, and the tuning range is 200 Hz.



## **Magnetic shield**

- 2 layer of magnetic shield (Ota's Permalloy PC) reduce the geo magnetic field to 10 mT.
- Experimental result shows good agreement with simulation.











## **SC** solenoid

- SC solenoid was designed for emittance measurement.
- The focal length is 100 mm for 2MeV beam.
- Coil is cooled by conduction cooling from 2-Phase line.









Peak Hz =3.06±0.31 kG (CST= 2.95 kG, Opera2D=2.90 kG)

wire	value
Material	NbTi/Cu
Manufacturer	Furukawa F54/4.2/65
Resistance of unit length @RT	0.597 (mOhm/cm)
Resistance of unit length @20K	2.84 (uOhm/cm)
Number of turns	1685
Operation current	~ 10.3 A
Max field on wire	~ 0.35 T
Load line ratio	~20 % @8K

Offline measurement with 4K helium bath





## **90 deg. Bending magnet**

Magnetic field (mT)

80

60

40

20

0

2



Hysteresis measurement Estimation of beam size



![](_page_10_Figure_4.jpeg)

90 deg. Bending magnet was designed for 2 MeV beam energy evaluation.

The hysteresis curve was measured.

![](_page_10_Picture_7.jpeg)

![](_page_10_Picture_8.jpeg)

at center magnet

### Laser system

#### Photocathode image

![](_page_11_Picture_2.jpeg)

- Synchronization signal is 162.5 MHz.
  - Borrowed laser system from cERL and STF.
- Laser position is aligned by using double slit and CCD camera.

## Reference signal, 1300 MHz from cavity pick up. Synchronization signal 162.5 MHz

![](_page_11_Figure_7.jpeg)

![](_page_11_Picture_8.jpeg)

![](_page_11_Picture_9.jpeg)

![](_page_11_Picture_10.jpeg)

![](_page_11_Picture_11.jpeg)

## **LLRF and Data taking**

- Center for Applied Superconducting Accelerator 応用超伝導加速器センター
- A laser synchronization circuit was added to the existing LLRF.
- The laser frequency follows the cavity frequency.
- Data taking system was updated to EPICS server and CS-studio.

![](_page_12_Figure_5.jpeg)

## **Assembly procedure**

- Apply HPR to cavity with jacket.
- Assembled in clean room.
- Baking at out of clean room

![](_page_13_Picture_4.jpeg)

![](_page_13_Picture_5.jpeg)

![](_page_13_Picture_6.jpeg)

#### Transport to horizontal test cryostat area

![](_page_13_Picture_8.jpeg)

## **Assembly procedure**

![](_page_14_Picture_1.jpeg)

- All vacuum components are assembled in local clean booth.
  - The connection process was performed in different locations for 6-7 times.
- Pumped with slow pumping unit (pumping speed is 0.6 L/min, purge speed is 0.2 L/min)

![](_page_14_Figure_5.jpeg)

## **Cooling procedure**

- Pre-cooling by He gas heat exchanged with LN2 for 2 days.
- 2K measurement used LHe 1000 L /day.
  - Measurable time depends on precooling.
    - 1st day of 2K measurement is 8 hours
    - 2<sup>nd</sup> day of 2K measurement is more than 10 hours

![](_page_15_Figure_6.jpeg)

![](_page_15_Picture_7.jpeg)

![](_page_15_Picture_8.jpeg)

![](_page_15_Picture_9.jpeg)

#### 1000L LHe dewar

Test # and condition		
HPR		
2 <sup>nd</sup> HT	w/o cathode rod	
HPR+beamline+pre		
3 <sup>rd</sup> HT	w/o cathode rod	
4 <sup>th</sup> HT	w/ cathode rod	
HPR+beamline+SCsol+pre		
6 <sup>th</sup> HT	w/ cathode rod	
1 <sup>st</sup> HT is cooling only.		

5<sup>th</sup> HT is failed by RF cable trouble

## Horizontal test result

![](_page_16_Picture_1.jpeg)

- The maximum Esp was limited around 20-30MV/m by FE or by quench.
- Although the cavity was completely disassembled and applied HPR, FE could not remove.
- We suspect the FE source come into the cavity in complicated local clean booth work.
- We tried a beam test following 6<sup>th</sup> HT. But cathode transfer trouble was happened, and cathode lifetime was too short. Unfortunately, we could not observe beam.

![](_page_16_Figure_6.jpeg)

Test # and condition		
HPR		
2 <sup>nd</sup> HT	w/o cathode rod	
HPR+beamline+pre		
3 <sup>rd</sup> HT	w/o cathode rod	
4 <sup>th</sup> HT	w/ cathode rod	
HPR+beamline+SCsol+pre		
6 <sup>th</sup> HT	w/ cathode rod	
1 <sup>st</sup> HT is cooling only.		

5<sup>th</sup> HT is failed by RF cable trouble

#### **Plan for deliver the cavity to MSU/FRIB**

![](_page_17_Picture_1.jpeg)

- We shipped the cavity and beam test system except cryomodule, laser, and LLRF.
- We will combine KEK SRF gun and WiFEL cryomodule and continue L band SRF gun study.

![](_page_17_Figure_4.jpeg)

![](_page_18_Picture_0.jpeg)

# Summary

- KEK SRF gun was built to evaluate the fundamental performance of the SRF gun.
- Esp reach the target value by applying EP and HPR in VT because assembly procedure is well established.
  - Esp= 76 MV/m w/o cathode, Esp=61.5 MV/m w/ cathode (target Esp=41.9 MV/m)
- The gradient was significantly lower in HT. This was due to the complicated procedure.
  > Esp=42 MV/m (6<sup>th</sup> HT)
- We made a beam test components to evaluate gun cavity. Each components were evaluated in offline.
  - > The photocathode chamber has a lot of issues, load lock system and short lifetime.
- We shipped the cavity and beam test system except cryomodule, laser, and LLRF. And combine KEK SRF gun and WiFEL cryomodule and continue the SRF gun study.