


# MESA – a fully instrumented ERL project for nuclear and particle physics experiments

- Layout of MESA and experimental setups
- Current status of realization
- MESA schedule

ERL Workshop 2022  
October 3rd 2022  
Florian Hug presenting work of the  
MESA group




Partially supported by the  
**European Union's Horizon  
2020 Research and Innovation  
programme under Grant  
Agreement No 101004730  
(iFAST).**



# MAMI and MESA at KPH Mainz

- MAMI is operating since >25 years at KPH
- In 2012 funding of PRISMA cluster of excellence has been granted including a new accelerator project:



Mainz Energy Recovery Superconducting Accelerator (MESA) to be built in the existing facility

- In June 2015 DFG granted a research building to JGU „Center for Fundamental Physics (CFP)“ including an extension for MESA halls

# What is MESA and what is it good for?


MESA Mainz Energy-recovering Superconducting Accelerator

ERL is one component in the European accelerator “roadmap”

Quotation from: Andrew Hutton, ERL Roadmap panel symposium, June,3, 21

“Unique feature of MESA: First completely instrumented ERL facility for particle and nuclear physics”

Detailed informations on MESA experiments:  
Talk by Kurt Aulenbacher (presented by F. Hug) on Wednesday



# MESA Status




Breakthrough between Experimental CFP-1 and KPH halls (September, 7, 2021)



In June 2021  
it was officially  
announced that  
full occupancy of  
CFP-1 will be  
possible in  
**mid/end 2023**  
Representing a  
shift by almost  
**two years**

Delay was anticipated early, Mitigation strategy est. 2019....

# Beschleunigte Aufbaumassnahme MESA (BAM)




# MESA Accelerator Layout

Double sided recirculation design with normal-conducting injector and superconducting main linac

Two different modes of operation:  
(1300 MHz CW beam)


- EB-operation (P2/BDX experiment):  
**polarized** beam,  
up to  $150 \mu\text{A}$  @ 155 MeV
- ERL-operation (MAGIX experiment):  
(un)polarized beam,  
up to **1 (10) mA** @ 105 MeV



# MESA Accelerator Layout

Source and Beam preparation system:  
MESA Low Energy Beam Apparatus  
(MELBA)


- Defines the quality of the MESA beam



# MESA Accelerator Layout

MESA injector linear accelerator:  
Milli-AMpere-Booster (MAMBO)

In ERL mode, all beam power  
(up to 50kW) comes from the injector:  
MAMBO is the „powerhouse“  
of MESA



# MELBA Tests

## Old MELBA Test set-up

- Operation with up to 150keV beam and up to 10mA beam current
- MELBA was dis-assembled and put in storage due to start of hall renovation for MESA

PhD Theses completed

S. Friederich (2019)

R. Kempf (2020)


C. Matejcek (2021)

P. Heil (2021)



## Surface photovoltage in NEA GaAs at 10mA


S. Friederich et al. doi:10.18429/JACoW-IPAC2019-TUPGW028




No.	$QE_0$
①	2.40 %
②	1.55 %
③	1.15 %
④	0.85 %
⑤	0.50 %
⑥	0.39 %

## Transverse emittance

C. Matejcek et al. doi:10.18429/JACoW-IPAC2019-TUPGW028



## Longitudinal emittance




# Source/beam preparation (MELBA) layout

Photosource „STEAM“  
(polarized beam)

High bunch charge/beam  
current source  
(unpolarized beam)

Double scattering  
Mott polarimeter




Spin Manipulation

Circular  
Chopper

f/2f buncher  
cavities


To MAMBO  
injector

# Injector working principle




S. Friederich et al: IPAC 2021

# MELBA/MAMBO: final Accelerator Layout



- In a huge number of online meetings the arrangement of components has been planned
- Several issues raised by results of test experiments and MAC suggestions adressed (improved corrector magnets, BPM's for P2, Spin manipulation. 5MeV polarimeter... )
- „freezing“ & start assembly in 2/2022

# OPAL simulation results for complete injector




Location	$s$ m	$\sigma_x$ mm	$\sigma_y$ mm	$\sigma_s$ mm   °   ps	$\epsilon_{x,n,rms}$ mm mrad	$\epsilon_{y,n,rms}$ mm mrad	Energy MeV	$\Delta E_{rms}$ keV
Initial	0.3	0.2	0.2	8.1   23.1   50.0	0.03	0.03	0.1	0
MELBA exit	9.4	0.8	0.7	0.8   2.3   4.9	0.22	0.20	0.1	1
Injector exit	20.4	1.3	1.3	0.2   0.3   0.6	0.40	0.35	5.1	3

S. Friederich et al: IPAC 2021

# Injector Status today



# Impact of Pandemic on MESA construction- RF-vendors




- RF amplifiers & MAMBO Sections were ordered in 2019
- ...Based on existing prototypes
- Supplier for RF-amplifiers went bankrupt in 12/2020
- New owner JEMA France continues contract
- Successful SAT of 4\*550 Watt basic module in 9/2021
- Delivery of first (biggest) amplifier **now scheduled for end 22**
- Auxiliary systems (LLRF, vacuum, diagnostics), expected to be ready before amplifier delivery

74 kW 1300 MHz amplifier (CAD drawing)  
Vendor: JEMA France (former SPE)  
Amplifier batch: 1\*74, 3\*54, 4\*15 kW


# Cryomodules

MESA ELBE-Enhanced Cryomodule (MEEC):

Superconducting RF-cavities provide large energy gain on small footprint and enable Energy-recovery-Linac (ERL)-operation



# SRF-System: MEEC-Cryomodules



3.5 meter

Specs: 25 MeV Energy gain at <40 Watt thermal loss at 2 Kelvin

# Production of 2 Cryomodules



2015: 2 MEEC's ordered at RI Research Instruments GmbH

Until 2017 SRF testing infrastructure became available at HIM

9/2018: First cryomodule does not meet specs at HIM → refurbishment by vendor,

3/2019: Second tested cryomodule achieves specs during test at HIM/Mainz


8/2020 :refurbished cryomodule tested and fulfills specs.



Cryomodules miss dynamical specs slightly but fulfill static specs by wide margin  
→ On average the Helium consumption is estimated to be less than anticipated.

PhD thesis Timo Stengler  
See also: T. Stengler et al. Proc. SRF 2019  
doi:10.18429/JACoW-SRF2019-TUP041

# MESA/P2 construction- Cryogenics (main issues only...)




Coldbox with Compressor  
(2\*, "separate solution" )


- Upgrade of L280 plant will start May 2022
- Plant can serve MESA + P2 solenoid
- P2-refrigerator – cooling of Hydrogen target - needs separate cryoplant
- Negotiations with companies specialized on cryogenic piping ongoing

(More about MESA SRF in a dedicated talk on Tuesday)

# Lattice ERL/EB mode




# Lattice: ERL mode start to end simulation




ERL-Lattice – not completely symmetrical due to energy (gain) dependent focussing of RF-structures.

# Recirculation arcs optics

- Optics symmetric with respect to the middle of the long straight section.  
 $\alpha=0$  in the middle of the return arc
- Return arc is free of transverse and vertical dispersion
- Longitudinal dispersion  $r_{56}$  can be adjusted by changing the gradients of the middle quadrupoles in the  $45^\circ$  sections
- Total length of 1<sup>st</sup> return arc: ~45m  
difference in time-of-flight for beams of 15 MeV and 30 MeV:  
 $\Delta t=60.5 \text{ ps} \rightarrow 28.3^\circ$  in RF @ 1.3 GHz
- Path length adjustment needed  
(2 cm minimum  $\approx 35^\circ$  RF-phase)  
for complete flexibility in beam energy  
(chicane or moveable magnets)




# BBU investigation



13mA BBU limit at Target  
in 4pass configuration 2up/2down  
(without countermeasures)

PhD thesis Christian Stoll,  
See also: C. Stoll and F. Hug: proceedings IPAC 2019  
doi:10.18429/JACoW-IPAC2019-MOPGW025




Note:  
Technical limitation: Heating  
of HOM coupler in TESLA cavities.  
(~1mA CW estimation, but needs to  
be determined experimentally)


# MESA construction- Magnets

Magnet Basic parameters well known and not demanding  
Task before tendering:

- Determine lattice tolerance against field errors
- avoid unnecessary precision requirements
- Tendering started September 2022



MESA ERL Mode beta-functions



## Spreader/recombiner




Figure 1.2: Sketch of the beam separation for uneven turns.

## ERL-ARC (MAGIX)

1.1.3 MAGIX beam line




Figure 1.4: Sketch of the beam line for the internal experiment MAGIX.

## EB-Line (P2)

1.1.4 P2 beam line




Table 1.1: Parameters of the MARC bending dipoles.

	Quantity	Energy	Angle	Radius	Gap	B-field
MARC 1	4	30 MeV	45°	700 mm	40 mm	143 mT
MARC 2	4	55 MeV	45°	700 mm	40 mm	262 mT
MARC 3	4	80 MeV	45°	700 mm	40 mm	381 mT
MARC 4	4	105 MeV	45°	700 mm	40 mm	500 mT
MARC 5	4	130 MeV	45°	700 mm	40 mm	619 mT

Table 1.3: Parameters of the dipoles of the vertical beam separation for uneven turns. For dipoles with multiple beams only the values for the lowest energy are shown.

Dipole	Quantity	Energy	Radius	Angle	Gap	B-field
A <sup>2</sup>	2	30 MeV	989.7 mm	38.79°	40 mm	101 mT
B	4	30 MeV	718.3 mm	38.79°	40 mm	139 mT
C	2	30 MeV	989.7 mm	38.79°	40 mm	101 mT
D <sup>2</sup>	2	80 MeV	1084.6 mm	14.15°	40 mm	246 mT
E <sup>2</sup>	2	80 MeV	966.9 mm	27.74°	40 mm	276 mT
F	2	80 MeV	966.9 mm	27.74°	40 mm	276 mT
G	2	80 MeV	1084.6 mm	14.15°	40 mm	246 mT
H	2	80 MeV	2639.2 mm	13.59°	40 mm	101 mT
F'	2	130 MeV	1571.1 mm	16.64°	40 mm	276 mT
G'	2	130 MeV	1762.4 mm	8.33°	40 mm	246 mT
H'	2	130 MeV	4288.8 mm	8.31°	40 mm	101 mT

Table 1.5: Parameters of the MAGIX beam line dipoles. The dipole type R stands for rectangular and S for sector magnet.

Position	Quant.	Type	Energy	Angle	Radius	Gap	B-field
ARC 1	2	R	105 MeV	22.5°	770 mm	40 mm	455 mT
ARC 2 <sup>4</sup>	2	S	105 MeV	45.0°	700 mm	TBD	500 mT
ARC 2	2	S	105 MeV	22.5°	770 mm	40 mm	455 mT
Chicane	2	R	105 MeV	12.1°	1917 mm	40 mm	183 mT
Chicane	1	R	105 MeV	24.1°	958 mm	40 mm	366 mT

Table 1.6: Parameters of the P2 beam line dipoles. The dipole type R stands for rectangular and S for sector magnet.

Position	Quant.	Type	Energy	Angle	Radius	Gap	B-field
DBA 1	2	S	155 MeV	45°	1000 mm	30 mm	517 mT
DBA 2	2	S	155 MeV	40°	900 mm	30 mm	574 mT
DBA 3	2	R	155 MeV	10°	1500 mm	30 mm	345 mT
dog leg	2	R	155 MeV	10°	1500 mm	30 mm	345 mT
ARC	2	S	155 MeV	45°	1000 mm	30 mm	517 mT
ARC	2	S	155 MeV	60°	1000 mm	30 mm	517 mT

# Summary

- MESA is a fully instrumented ERL facility for nuclear and particle physics experiments
- Construction of injector is ongoing, main accelerator construction will be started as soon as the new building is ready (Jan 2023)
- Most critical components are tested already. „Uncritical“ components are in the process of tendering
- First beams to at low energy (15-55 MeV, 1 Recirculation) to the experiments can be expected 2 years after building occupancy